



**Mechanical & Building Solutions**

# BIM for the Mechanical Contractor From VDC Strategy to Coordination Success

[www.harrell-fish.com](http://www.harrell-fish.com) | (812) 339-2579 |



# My Timeline



**2003**  
**Start BCM**



**2004**  
**MCA Purdue**



**2006**  
**Married Julayne!**



**2007**  
**Graduate**



**2007**  
**Start my Career**  
**APM**



**2016**  
**Fritz is Born!**



**2014**  
**Director of VDC &**  
**Fab Operations**



**2013**  
**Luke is Born!**



**2008**  
**PM**



**2018**  
**Leadership Team**



**2024**  
**MEP Innovations Committee**



**2024**  
**HFI Executive Team**



**2025**  
**President**



## OUR PURPOSE:

Making a difference for our employees, clients, industry & community as a great enduring company.

### Core Values

- We will do whatever it takes.
- We take pride in quality work.
- We believe in getting the job done.
- We will lead to make our teams better.
- We care about each other, our clients, and our partners.
- We look forward to the next big challenge.
- We are always looking to improve.
- We make safety personal.
- We believe in acting with professionalism, integrity, and honesty.

### Brand Promises

- Deliver Results
- Provide Solutions
- Act with Urgency

### Theme

Make A Difference

### BHAG

Be the best in the Midwest by 2028!

### Focused On:

- Safety
- Employee Satisfaction
- Client Satisfaction
- Community Engagement
- Industry Improvement
- Repeat Business
- Negotiated Work
- Profitability

# Virtual Design & Construction (VDC)

**Creating a virtual model of a construction project before physical work begins and then extracting this data to assist the physical work**

## **VDC Tools**

- **3D Modeling & Design**
- **BIM (Building Information Modeling) Coordination**
- **Fabrication Prep/Spool Drawings**
- **Robotic Total Station Layout**
- **3D Laser Scanning/Point Cloud Creation**

# AGENDA

- **BIM Phase I**
- **BIM Phase II**
- **Fabrication Train**
- **Best Practices**
- **MCAA VDC Flow Chart**



# BIM Phase 1

Modeling/Population/Detailing




Coordination




Clash Resolution




Sign-off










## Model Content

- All Trades Represented
  - Insulation
  - Supports
- Supplemental Steel
  - Clearance zones
- Existing Conditions/Laser Scan
- Manufacturer Based Content











# Space Management


---

- Stratification
- Future Projects
- **Maintenance**
  - Clearance Zones – Coil Pulls
  - Clearance Zones – Maintenance Access
  - Clearance Zones – Electrical Clearances
  - Access to Valves
  - Access to Pull Boxes
  - Access to Cable Trays



# Laser Scanning





# BIM Phase 2



**TFL/Field Layout Files**



**Bill of Materials (BOM's)**




**Fabrication Iso's for foremen input**



**Spool Sheets & Hanger Schedules**



**Spool Maps & Shop Drawings/Install Drawings**



# Bill of Materials

<2558 - 12E - BOM - Pipe>						
A	B	C	D	E	F	G
Size	Length	Material Description	Package Id	Package Name	Shipping Info	System Type
2"	242' - 5 7/8"	Charlotte CI NH-2 Pipe	2558	12E W Cast Iron		Sanitary
3"	6' - 7 3/8"	Charlotte CI NH-2 Pipe	2558	12E W Cast Iron		Sanitary
4"	115' - 9 1/2"	Charlotte CI NH-2 Pipe	2558	12E W Cast Iron		Sanitary

<2558 - 12E - BOM - Fitting>							
A	B	C	D	E	F	G	H
Count	Nominal Size	Alternate Description	Element Package ID	Element Package Nam	Shipping Info	System Type	Family and Type
25	2"	Charlotte CI NH-4 Quarter Bend NHxNH	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-4 Quarter Bend NHxNH: Charlotte CI
41	2"	Charlotte CI NH-12 45° Elbow	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-12 Eighth Bend NHxNH: Charlotte CI
42	3"	Charlotte CI NH-12 45° Elbow	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-12 Eighth Bend NHxNH: Charlotte CI
36	4"	Charlotte CI NH-12 45° Elbow	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-12 Eighth Bend NHxNH: Charlotte CI
1	2"	Charlotte CI NH-14 22.5° Elbow	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-14 Sixteenth Bend NHxNH: Charlotte CI
1	4"	Charlotte CI NH-16 Short Sweep NH x NH	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-16 Short Sweep NHxNH: Charlotte CI
16	4"x4"x2"	Charlotte CI NH-20 Reducing Wye	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-20 Reducing Wye NHxNHxNH: Charlotte CI
1	4"	Charlotte CI NH-20 Wye	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-20 Wye NHxNHxNH: Charlotte CI
17	4"	Charlotte CI NH-22 Combination	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-22 Combination NHxNHxNH: Charlotte CI
1	3"x3"x2"	Charlotte CI NH-22 Reducing Combination	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-22 Reducing Combination NHxNHxNH: Charlotte CI
16	4"x4"x2"	Charlotte CI NH-22 Reducing Combination	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-22 Reducing Combination NHxNHxNH: Charlotte CI
1	2"	Charlotte CI NH-28 Sani-Tee	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-28 Sanitary Tee NHxNHxNH: Charlotte CI
1	3"x2"	Charlotte CI NH-40A Short Reducer	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-40A Short Reducer NHxNH: Charlotte CI
2	4"x2"	Charlotte CI NH-40A Short Reducer	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-40A Short Reducer NHxNH: Charlotte CI
17	2"	Charlotte CI NH-42 P-Trap	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-42 P-Trap NHxNH: Charlotte CI
15	4"	Charlotte CI NH-50 Blind Plug	2558	12E W Cast Iron		Sanitary	Charlotte CI NH-50 Blind Plug NH: Charlotte CI
39	2"	Fernco Qwik Cap	2558	12E W Cast Iron		Undefined	Fernco PVC Qwik Cap CI NH: Fernco PVC
236	2"	Mission C-HW Coupling	2558	12E W Cast Iron		Sanitary	Mission Rubber C-HW Heavy Weight Cplg NHxNH: Mission Rubber
6	3"	Mission C-HW Coupling	2558	12E W Cast Iron		Sanitary	Mission Rubber C-HW Heavy Weight Cplg NHxNH: Mission Rubber
208	4"	Mission C-HW Coupling	2558	12E W Cast Iron		Sanitary	Mission Rubber C-HW Heavy Weight Cplg NHxNH: Mission Rubber




<2558 - 12E - BOM - Pipe Accessories>							
A	B	C	D	E	F	G	H
Count	Nominal Size	Alternate Description	Element Package Id	Element Package N	System Type	Family and Type	Shipping Info
39	2"	Anvil CS Fia-261 Riser Clamp	2558	12E W Cast Iron	Undefined	Anvil CS Fia-261 Riser Clamp Plain Finish; Anvil CS	

[illegible]

# Spooling

Foreman input is critical

- Weight
- Dimensions
- Logistics – how is it getting in the building









# Spooling = LEGO

Building something big,  
piece by piece

HOW DO YOU EAT AN ELEPHANT?

ONE BITE  
AT A TIME



# Fabrication Train



**Material Ordering**



**Material Receiving**



**Fabrication**




**Ship to the jobsite**




**Just in time delivery to the jobsite**






















# Best Practices


- **Face to face meeting with onsite CM management**
  - **Explain BIM Phase 1, BIM Phase 2, and Fabrication Train**
  - **How are we going to construct the building?**
  - **Sequencing**
    - **Time for layout of sleeves/imbeds prior to mesh/rebar**
    - **Time for layout of cores/hangers prior to priority wall framing**
    - **Main distribution fabrication install prior to wall framing**
- **Manageable Sequence Areas**
  - **Fire Hose vs Garden Hose**
  - **Work with the CM to incorporate the smaller sequences into the project schedule**
- **BIM Coordination Team Structure**
- **Mechanical Contractor Team Structure**
- **Daily/Weekly coordination with the internal jobsite team (Foreman, PM, VC)**

# Schedule Alignment



**FABRICATION TRAIN IS  
CONTINUOUS. IT  
DOESN'T STOP.**

- **Depends on effective organization**
- **Requires accurate incorporation of bulletins and changes**
- **Depends on high-quality and prompt information**






## BIM Coordination Team

- BIM Coordination Lead
- BIM Detailers for all Trades
- Project Managers
- Superintendents/Foremen
- Architect/Engineer Team
- Owner Group (Construction & Maintenance)


## Mech Project Team

- Superintendents/Foremen
- Project Manager
- VDC/BIM Lead
- Fabrication Team
- Procurement Team
- Logistics Team



Call In	Job #	Job Name	Package Name	Package ID	OM received	BOM Due Date	Drawing Due Date	Install Drawing Comple...	Fabrication Due Date	% Complete	Jobsite Delivery Due Date	Har
	4321	IUH 345 MP	9E PP CW SS	1834	<input type="checkbox"/>	07/31/25	08/07/25	<input type="checkbox"/>	08/21/25	100%	08/22/25	
	4321	IUH		1746	<input type="checkbox"/>	07/31/25	08/07/25	<input type="checkbox"/>	08/21/25		08/22/25	
	4321	IUH 345 MP	LVL5-O12NC SAV TCV	1824	<input checked="" type="checkbox"/>	02/06/25	02/13/25	<input type="checkbox"/>	02/27/25	100%	02/28/25	
			Core Locations	4430	<input checked="" type="checkbox"/>	05/23/25	05/30/25	<input type="checkbox"/>	06/13/25		06/16/25	
	4443	Needmore	Needmore Coil Pack Fabricatio	Needmore	<input type="checkbox"/>	06/12/25	06/19/25	<input type="checkbox"/>	07/03/25	99%	07/04/25	
	4443	Shawswick	Shawswick Coil Pack Fabricatic	Shawswic	<input type="checkbox"/>	06/12/25	06/19/25	<input type="checkbox"/>	07/03/25	99%	07/04/25	
	4321	IUH 345 MP	LVL14-T12C VAV TCV	2400	<input type="checkbox"/>	06/16/25	06/23/25	<input type="checkbox"/>	07/07/25	87%	07/08/25	
	4321	IUH 345 MP	LVL14-T12N VAV TCV	2401	<input type="checkbox"/>	06/16/25	06/23/25	<input type="checkbox"/>	07/07/25	84%	07/08/25	
	4321	IUH 345 MP	LVL14-T12S VAV TCV	2402	<input type="checkbox"/>	06/16/25	06/23/25	<input type="checkbox"/>	07/07/25	82%	07/08/25	
	4430	Simtra Greenl	BFP Stands	2580	<input type="checkbox"/>	07/09/25	07/16/25	<input type="checkbox"/>	07/30/25		07/31/25	
	4430	Simtra Greenl	1D PP2 Hangers	2622	<input checked="" type="checkbox"/>	07/15/25	07/22/25	<input type="checkbox"/>	08/05/25	100%	08/06/25	1
	4457	NAF R.O Tank		Erik H Fat	<input type="checkbox"/>	07/17/25	07/24/25	<input type="checkbox"/>	08/07/25		08/08/25	
	4471	TMMI		Hangers	<input type="checkbox"/>	07/17/25	07/24/25	<input type="checkbox"/>	08/07/25		08/08/25	
	4321	IUH 345 MP	16E MP Copper	2324	<input checked="" type="checkbox"/>	11/21/25	11/28/25	<input type="checkbox"/>	12/12/25	100%	12/13/25	
	4321	IUH 345 MP	PHB MP CD	2610	<input type="checkbox"/>	07/24/25	07/31/25	<input type="checkbox"/>	08/14/25	100%	08/15/25	
	4321	IUH 345 MP	PHB MP Copper	2526	<input type="checkbox"/>	07/24/25	07/31/25	<input type="checkbox"/>	08/14/25	100%	08/15/25	
	4321	IUH 345 MP	PHD MP Copper	2528	<input type="checkbox"/>	07/24/25	07/31/25	<input type="checkbox"/>	08/14/25	100%	08/15/25	
	4321	IUH 345 MP	PHF MP Copper	2529	<input checked="" type="checkbox"/>	07/24/25	07/31/25	<input type="checkbox"/>	08/14/25	100%	08/15/25	
	4321	IUH 345 MP	PH D PP CW Copper	2530	<input checked="" type="checkbox"/>	07/24/25	07/31/25	<input type="checkbox"/>	08/14/25	100%	08/15/25	
	4321	IUH 345 MP	PH D PP HW Copper	2531	<input checked="" type="checkbox"/>	07/24/25	07/31/25	<input type="checkbox"/>	08/14/25	100%	08/15/25	
	4321	IUH 345 MP	PH F PP CW Copper	2532	<input type="checkbox"/>	07/24/25	07/31/25	<input type="checkbox"/>	08/14/25		08/15/25	
	4321	IUH 345 MP	PH F PP HW Copper	2533	<input type="checkbox"/>	07/24/25	07/31/25	<input type="checkbox"/>	08/14/25		08/15/25	
	25-0141760	Service		Water Boi	<input type="checkbox"/>	07/25/25	08/01/25	<input type="checkbox"/>	08/15/25		08/18/25	
	4321	IUH		Level 15 C	<input type="checkbox"/>	07/25/25	08/01/25	<input type="checkbox"/>	08/15/25		08/18/25	

# Project Acquisition




### Turnover Meeting

EM PM FM VC VM SF BD


### Planning for Success

1. Do not start planning /condensed specifications without approved material submittals.
2. Project Manager needs to facilitate collaboration through the understanding of VDC process, BIM tools, planning personnel, as well as BIM scope, schedule, deliverables and deadlines. PM to take an active role in managing BIM labor.
3. Do Project requirements align with the teams skill set or will additional support/ training be needed?
4. Early review contract documents for issues that go beyond the VDC scope for Coordination, and therefore Identify potential Change orders.


# Pre-Construction



## Planning/Coordination



# Drawing Production, Pre-Fabrication & Installation



# Post Job Review

360 Feedback:

## Conduct Post-Mortem Meeting

These are the suggested Agenda topics and discussion points to be addressed. The following questions can help guide discussion and analysis of the project.

- How did final costs compare to estimated costs?
- What major assumptions were used in estimating the job? Were they accurate?
- What major variances occurred? What caused them?
- How did the time spent on VDC compare to the estimate?
- What factors affecting VDC hours should be considered for future planning?
- Did the VDC process follow the original schedule?
- How good were company relations with the following INTERNAL groups?
  - Estimating Manager
  - Operations Manager
  - Project Manager
  - Project Engineers
  - Purchasing Manager
  - Shop Foreman/Superintendent
  - Field Foreman/Superintendent
  - Safety Director
- How good were company relations with the following EXTERNAL groups?
  - Project Owner/Owner Rep.
  - Design Professionals
  - General Contractor or Construction Manager
  - Subcontractors
  - Other project Trades
  - Suppliers and Manufacturers
- How well did the GC/CM treat the company during the VDC process in terms of:
  - Scheduling of meetings
  - Clash Detection/Resolution
  - Compared to other trades
  - Communication during installation
- Did the project team follow through with goals and procedures established during the pre-planning, particularly those for:
  - VDC Execution and Scope
  - Document controls and Submittals
  - Prefabrication and Shop drawings
- What were the project team's overall strengths
- What would the project team do differently on future projects

# Why VDC?

- **Increased Pre-planning**
  - Reduction in risk for contractor and client
  - Reduction in schedule impacts due to identifying conflicts early
- **Increased Fabrication Opportunity**
  - Major safety impact
    - Reduction of crew size on the job site.
    - Work done in safe environment and at safe height
  - Increased efficiency due to tooling and ergonomics
  - Increased ability to hit schedule
- **Positive side effects may include:**
  - Increased project performance
  - Increased client satisfaction
  - Increased repeat business



# Without VDC/FAB



# Q & A



# Resources

[Successful VDC Management Flowchart](#)

[Achieving Spatial Coordination through BIM – A Guide for Specialty Contractors.](#)